BRUHAT BANGALORE MAHANAGARA PALIKE
BYATARAYANAPURA DIVISION

Name of Worke: Construction of Drain From Chikkasiddappa Layout to SWD in Amruthahalli in Ward No. 07 Byatarayanapura

Draft Tender Schedule

Item No	Description of work	Unit	Total Quantity as per Estimation	Rate as per estimate in Rs.	
				In Figures	In Words
1	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete asper specifications.MORTH / Chapter 3(I No-19.1, P No-143)	Cum	1209.60	252.49	Rupees Two Hundred Fifty Two and Paise Forty Nine Only
2	KSRB2.8:ProvidingandFillinginfoundationwithgranite/trapbrokenmetal100mm.anddownsize,withapprovedsandincludinghandpacking,ramming,watering,includingcostofallmaterialsandlabourwithallleadandlift.completeasperspecifications.specification.No.KBS(P.No.7, I.No.2.15 of PW,P&IWTD S.R 2018-19)	Cum	189.00	2574.74	Rupees Two Thousand Five Hundred Seventy Four and Paise Seventy Four Only
3	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.3 of PWD SR 2018-19)	Cum	63.00	5408.12	Rupees Five Thousand Four Hundred Eight and Paise Twelve Only
4	KSRB 4 6.1:Providing and removingc entering, shuttering,s trutting, proppingetc., and removal off or mwork for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specifcation No.KBS4.6.2(P.No.16,I.No.4.28 of PW, P&IWTD SR 2018-19)	Sqm	126.00	273.48	Rupees Two Hundred Seventy Three and Paise Forty Eight Only
5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2(I No-4.31,P No-16)	Sqm	1512.00	379.48	Rupees Three Hundred Seventy Nine and Paise Forty Eight Only
6	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) P.No.18, I.No.4.48of PW,P&IWTD SR 2018-19)	Cum	352.80	5770.64	Rupees Five Thousand Seven Hundred Seventy and Paise Sixty Four Only
7	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.Specification No. KBS 4.6.3(I No-4.46.2,P No-18)	Tonne	29.99	75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three and Paise Ninety Six Only

Contractor

Executive Engineer
Bruhat Bangaluru Mahanagara Palike

"DTS APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ